

John's Office
- New CEO WS & 2 Monitors
- Dual purpose 3rd Monitor/TV hung on wall (55" Mount tight to wall - dealer supplied)

Server Room(SR)
- Wants 2 Storage Cabinets

Jeannett's Office
- Standard

Ron's Office
- All new
- CEO WS & 2 Monitors
- Monitor hung on wall (55" Mount tight to wall - dealer supplied)

Dave's Office
CEO WS & 3 Monitors


Conference Room
Screen for Projector

Conference Room
Projector - Hung on ceiling & Conference Phone
Projector needs a 2nd port for visitors with laptops

CTAS344 - Data&Voice3 Offices (Rev#2)
- SO59289



8038 YONGE ST. UNIT 25
TORONTO, ON L3T 7R9



- Telephone - 1 CAT5e Cable to nearest MDF, terminated on Rack Mounted Patch Panel
- Data - 1 CAT5e Cable to nearest MDF, terminated on Rack Mounted Patch Panels
- Digital Signage - 1 CAT5e Cable to nearest MDF, terminated on Rack Mounted Patch Panels
- CI/FAX - 1 CAT5e Cable to nearest MDF, terminated on BIX
- Callbox Antenna - 1 CAT5e cable to nearest MDF, Terminated on Rack Mounted Patch Panels
- Gemsys - 1 CAT5e Cable to nearest MDF, terminated on Rack Mounted Patch Panel
- CATV - 1 RG-6 cabled to Main MDF

GENERAL NOTES
DRAWINGS, SPECIFICATIONS AND RELATED DOCUMENTS ARE THE PROPERTY OF STEPHENSON DESIGN ASSOCIATES INC. AND ARE TO BE USED ONLY FOR THE PROJECT AND NOT FOR ANY OTHER PROJECT. STEPHENSON DESIGN ASSOCIATES INC. RETAINS ALL COMMON LAW, STATUTORY AND OTHER RESERVED RIGHTS, INCLUDING COPYRIGHT, IN THE DRAWINGS, SPECIFICATIONS OR RELATED DOCUMENTS. NO REPRODUCTION OF DRAWINGS, SPECIFICATIONS OR RELATED DOCUMENTS IS STRICTLY PROHIBITED WITHOUT THE EXPRESS WRITTEN CONSENT OF STEPHENSON DESIGN ASSOCIATES INC.

THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS AND DOCUMENTS FOR THIS PROJECT, INCLUDING MECHANICAL AND ELECTRICAL CONSULTANT'S DRAWINGS, AS WELL AS THE SPECIFICATIONS, ELEVATIONS, DETAILS, AND DOOR FRAME AND HARDWARE SCHEDULE DRAWINGS. IF THERE ARE ANY DISCREPANCIES, NOTIFY THE DESIGNER IMMEDIATELY.

CONTRACTOR SHALL COMPLY WITH ALL THE REQUIREMENTS AS NOTED IN THE CONTRACT DOCUMENTS, ALONG WITH ALL OTHER DOCUMENTS PROVIDED BY THE DESIGNER.

ALL WORK TO BE COMPLETED WITHOUT ANY INTERRUPTION TO BASE PLANTS. CONTRACTOR RESPONSIBLE FOR THE SUPPLY AND INSTALLATION OF ANY MATERIAL NOT SPECIFICALLY DRAWN OR NOTED BUT REASONABLY IMPLIED AND NECESSARY FOR THE COMPLETION OF THE SCOPE OF WORK.

PLUS/MINUS (+/-) DIMENSIONS REFER TO EXISTING CONDITIONS AND SHALL BE PROVIDED BY CONTRACTOR.

DO NOT SCALE DRAWINGS. THE CONTRACTOR SHALL CHECK AND VERIFY ALL DIMENSIONS AND REPORT ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK.

ALL WORK TO COMPLY WITH THE ONTARIO BUILDING CODE, LATEST EDITION, AND ALL OTHER AUTHORITIES HAVING JURISDICTION.

CONTRACTOR SHALL NOTIFY THE CHIEF BUILDING OFFICIAL OF THE SUBSTANTIAL COMPLETION AND COMPLETION OF THE STAGES OF CONSTRUCTION SET OUT IN SENTENCE 2.4.5.1(2) AND 2.4.5.2 OF THE BUILDING CODE, O. REG. 403/97 AS AMENDED. THE CONTRACTOR SHALL BE PRESENT AT EACH SITE INSPECTION BY AN INSPECTOR UNDER SENTENCE 2.4.5.3 OF THE BUILDING CODE.

STANDPIPE AND HOSE SYSTEM, FIRE ALARM AND EMERGENCY LIGHTING SYSTEM ARE REQUIRED, AND SHALL BE INSTALLED PRIOR TO OCCUPANCY OF FLOOR AREAS.

PORTABLE FIRE EXTINGUISHERS SHALL BE PROVIDED IN CONFORMANCE WITH ARTICLE 3.3.2.7 OF ONTARIO BUILDING CODE AND SECTION 6.2 OF THE LATEST EDITION OF THE ONTARIO BUILDING CODE.

ALL MATERIALS, SUPPLIES AND INSTALLED WITHIN THE OCCUPIED FLOOR AREAS SHALL HAVE A SMOKE/FLAME SPREAD RATING THAT MEETS THE REQUIREMENTS OF THE LATEST EDITION OF THE ONTARIO BUILDING CODE.

ADD OR RELOCATE EXIT SIGNAGE AND EMERGENCY LIGHTING PER O. REG. 403/97-3.2.7, 3.4.5.

CENTERLINE OF ALL NEW WALL SWITCHES, CONTROLS, HANDLES, OPERATORS, READERS AND DISPENSERS SHALL BE INSTALLED IN ACCORDANCE WITH ONTARIO BUILDING CODE BARRIER FREE DESIGN REQUIREMENTS.

- Cabling Notes:**
- All cable drops must have a 20' service loop coiled at ceiling before dropped
 - All cables in floor conduit must have a 20' service loop coiled under the counter
 - All cables must have a 20' service loop at MDF End.

SECOND LEVEL

Jean
- Standard AI with access to CBS

Tanya
- Standard

Main - office
Existing Non-CT MFP (in & out fax needed)
- CT Colour

Renee's Office
- CEO WS & 2 Monitors

Conference Room
2nd Port
TC wireless keyboard & mouse

70" TV
- Dealer provided
- CBS to supply mount

Charlotte's Office
- CEO WS & 2 Monitors

MAIN LEVEL

Dept Mgr's Office
- 2 TC
- 1 Telephone
- 1 Printer

HR's Office
- 1 TC
- 1 Telephone

Time well Scheduled Equipment
- extra data for future use
- iPad needed from CBS
- need to determine who will handle Install

Cash Office
- 1 Gemsys
- 1 TC
- 1 Telephone
- 2 extra

GENERAL LEGEND

- AREA NOT IN SCOPE
- ROOM OR AREA NUMBER
- NOTE NUMBER

ABBREVIATIONS

- FR REFRIGERATOR
- MW MICROWAVE
- DW DISHWASHER
- CM COFFEE MACHINE
- KT KETTLE
- TO TOASTER
- MF MINI FRIDGE
- DWL DIRECT WATER LINE
- VM VENDING MACHINE
- PRT PRINTER
- FAX FAX MACHINE
- TM TABLE MODULE
- TV WALL MOUNT TV
- PRJ PROJECTOR

FURNITURE PLAN NOTES

- ALL DISCREPANCIES IN THE DRAWINGS SHALL BE REPORTED TO SDA FOR FURTHER CLARIFICATIONS PRIOR TO PROCEEDING WITH THE WORK.
- ALL SYSTEMS FURNITURE INDICATED ON THIS PLAN REPRESENTS DESIGN INTENT ONLY. REFERENCE FURNITURE DEALERS INSTALLATION FURNITURE PLANS FOR EXACT FURNITURE SPECIFICATIONS.
- CONTRACTOR TO COORDINATE WITH FURNITURE SUPPLIER PRIOR TO PLACEMENT OF FURNITURE.
- WHERE NOTED ON PLAN REFER TO AV SUPPLIER DRAWING AND SPEC PACKAGE AND ENGINEERING DRAWINGS FOR SPECIFIC AV AND ELECTRICAL REQUIREMENTS.
- CONTRACTOR TO COORDINATE WITH FURNITURE SUPPLIER TO DETERMINE THE BEST CORE DRILL LOCATIONS.
- CONTRACTOR TO COORDINATE WITH CLIENT OR FURNITURE SUPPLIER REGARDING SITE DELIVERY AND INSTALLATION SCHEDULE.
- REFER TO PARTITION PLAN FOR LOCATIONS OF BLOCKING IN PARTITION FOR AS REQUIRED FOR FURNITURE SUPPORT.

2	ISSUED FOR REVIEW	28/07/2018
1	ISSUED FOR REVIEW	24/07/2018
NO.	DESCRIPTION	DATE

CANADIAN TIRE CORPORATION
11311 99 STREET,
GRANDE PRAIRIE, AB

SCALE: 1/8" = 1'-0"

DATE: APRIL 13th 2018

DRAWN BY: KB

CHECKED BY: SS

DWG NAME: FURNITURE PLAN

PROJECT NO. 18-004-A-1

DWG NO. D1