







CTAS344 - CBS Legend
CCTV2 2nd Floor (Rev#5) -
SO#59289

-  CCTV Monitor - 1 RG-59 cabled to Server Rack in Main MDF (Computer Room)
-  CCTV Camera - 1 CAT5e Cables to nearest MDF, Terminated to Rack Mounted Patch Panels
-  Access Control - 1 Cat5e Cable to nearest MDF, terminated on rack mounted patch panel
-  Facial Recognition - 1 CAT5e Cable to nearest MDF, Terminated to Rack Mounted Patch Panels
-  Audio - 1 18/2 Power cabled to nearest MDF
-  Remote Cabinet - Alternate MDF's - cabled as Noted

Cabling Notes:

- 1 - All cable drops must have a 20' service loop coiled at ceiling before dropped
- 2 - All cables in floor conduit must have a 20' service loop coiled under the counter
- 3 - All cables must have a 20' service loop at MDF End, coiled in ceiling.

